



**FINISH KEY LEGEND**

FLOOR FINISH	CEILING HEIGHT
BASE FINISH	SPECIAL REQUIREMENTS
WALL FINISH	CEILING FINISH
F1 EXPOSED SEALED CONCRETE	B1 4" COVED VINYL
F2 EXPOSED STAINED & SEALED CONC.	B2 6" COVED VINYL
F3 V.C.T.	
F4 CARPET	
F5 GYM FLOOR (TO BE DETERMINED)	
WALLS	CEILING
W1 PAINT	C1 2 X 4 SUSP. ACOUSTICAL PANELS
W2 CERAMIC TILE UP 7" ON WET WALL PAINT OTHER WALLS AND ABOVE TILE	C2 2 X 4 SYSP. WITH VINYL COVERED GYPSUM PANELS
	C3 EXPOSED - PAINT ALL OVERHEAD
SPECIAL REQUIREMENTS:	

**WALL TYPE DESIGNATIONS**

W1 2-HOUR RATED FIRE BARRIER OF 8" C.M.U. UP TO 10'-0" A.F.F. OR 12'-0" A.F.F., PLUS WALL ABOVE UP TO BOTTOM OF DECK CONSTRUCTED OF 6" 25 GAGE STEEL STUDS AT 16" O.C. WITH 2-LAYERS 5/8" TYPE "X" GYPSUM BOARD ON BOTH SIDES. REFER DETAIL C6/A401.

W2 6" 25 GAGE STEEL STUDS AT 16" O.C. UP TO BOTTOM OF FLOOR OR ROOF DECK WITH 5/8" GYPSUM BOARD BOTH SIDES AND FILL WITH 5 1/2" ACOUSTIC BATS. (USE TYPE "X" GYPSUM BOARD WHERE NOTED TO BE 1-HOUR RATED.)

W3 3 5/8" 25 GAGE STEEL STUDS AT 16" O.C. UP TO BOTTOM OF ROOF OR FLOOR DECK WITH 5/8" GYPSUM BOARD BOTH SIDES AND FILL WITH 3 1/2" ACOUSTIC BATS. (USE TYPE "X" GYPSUM BOARD WHERE NOTED TO BE 1-HOUR RATED.)

W4 3 5/8" 25 GAGE STEEL STUDS AT 16" O.C. UP TO 6" ABOVE CEILING WITH 5/8" GYPSUM BOARD ON EXPOSED SIDE(S).

**GMP**  
**08-24-05**

**Use of Documents**  
The Drawings, Specifications, and other documents prepared by the Architect for this Project are instruments of the Architect's service for use solely with respect to this Project and shall not be used on other projects or additions to this Project without the Architect's written permission and due cooperation to the Architect.

**Scope Drawings**  
These drawings indicate the general scope of the project in terms of architectural design, concept, the dimensions of building, the major architectural elements and, in some cases, the structural, mechanical, and/or electrical systems. The drawings do not necessarily indicate or describe all work required for full performance and completion of the requirements of the Contract. On the basis of the general scope indicated or described, the trade contractors shall furnish all items material for the proper installation and completion of the work.

Drawn By: CAD  
Checked By: JWB  
Date: XX-XX-XX

Revisions:

Certified By: